Republic of the Philippines
Department of Education
Region X – Northern Mindanao
DIVISION OF OZAMIZ CITY
IBJT Compound, Carangan, Ozamiz City
Tel. No. (088)545-0988/Fax No. (088) 545-0990
Website: ozamiz.deped.gov.ph/Email: ozamiz.city@deped.gov.ph

Invitation to Bid for *THE PROCUREMENT OF CONSERVATION AND RESTORATION OF GABALDON SCHOOL BUILDING AT LABO CENTRAL SCHOOL FOR THE IMPROVEMENT OF GABALDON SCHOOL BUILDING*

1) The ***Department of Education, Division of Ozamiz City***, through the ***GAA for FY 2026*** intends to apply the sum of ***Six Million One Hundred Eighty One Thousand Six Hundred Eighty Four Pesos and 19/100 (P6,181,684.19)*** being the Approved Budget for the Contract (ABC) to payments under the contract for ***Conservation and Restoration of Gabaldon School Building at Labo Central School for the Improvement of Gabaldon School Building***. Bids received in excess of the ABC shall be automatically rejected at bid opening.

2) The ***Department of Education, Division of Ozamiz City*** now invites bids for ***Conservation and Restoration of Gabaldon School Building at Labo Central School for the Improvement of Gabaldon School Building.*** Completion of the Works is required ***120 Calendar Days***. Bidders should have completed, within ***10 years*** from the date of submission and receipt of bids, a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II. Instructions to Bidders (ITB).

3) Bidding will be conducted through competitive bidding procedures using a non-discretionary "pass/fail" criterion as specified in the IRR, otherwise known as the "New Government Procurement Act (NGPA)".

   Bidding is restricted to Filipino citizens/sole proprietorships, cooperatives, and partnerships or organizations with at least sixty percent (60%) interest or outstanding capital stock belonging to citizens of the Philippines.

4) Interested bidders may obtain further information from ***Department of Education, Division of Ozamiz City*** and inspect the Bidding Documents at the address given below from ***8:00 a.m. – 12:00 noon and 1:00 – 5:00 p.m., Monday to Friday***.

5) A complete set of Bidding Documents may be acquired by interested bidders on ***September 25, 2026*** from the address below *and upon payment of the applicable fee for the Bidding Documents, pursuant to the latest Guidelines issued by the GPPB, in the amount of* ***Ten Thousand Pesos*** **(P10,000.00).**

   It may also be downloaded free of charge from the website of the Philippine Government Electronic Procurement System (PhilGEPS) and the website of the Procuring Entity, provided that bidders shall pay the applicable fee for the Bidding Documents not later than the submission of their bids.

6) The ***Department of Education, Division of Ozamiz City*** will hold a Pre-Bid Conference on ***September 25, 2026;2:00PM*** at ***Division Office Boardroom 2nd Floor, Division of Ozamiz City, IBJT Compound, Carangan, Ozamiz City*** and/or through video conferencing via *google meet with the link meet.google.com/utu-xmaj-pkh,* which shall be open to prospective bidders.

7) Bids must be duly received by the Bids and Awards Committee (BAC) Secretariat through manual submission at the address indicated below on or before ***October 7, 2026 at 2:00 PM****.* Late bids shall not be accepted.

8) All Bids must be accompanied by a Bid Security in any of the acceptable forms and in the amount stated in **ITB** Clause 16.

9) Bid opening shall be on ***October 7, 2026 at 2:00 PM*** at ***Division Office Boardroom 2nd Floor, Division of Ozamiz City, IBJT Compound, Carangan, Ozamiz City****.* Bids will be opened in the presence of the Bidders' representatives who choose to attend the activity.

10) The ***Department of Education, Division of Ozamiz City*** reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Section 70 of R.A. No. 12009, without thereby incurring any liability to the affected bidder or bidders.

12) For further information, please refer to:

Jeffrey S. Libor
Chair, BAC Secretariat
DepEd, Division of Ozamiz City
IBJT Compound, Carangan, Ozamiz City
Tel No. (088)545-0988
Cell No. 0945-221-4098
Website address: www.ozamiz.deped.gov.ph
Email address: jeffrey.libor@deped.gov.ph

September 17, 2026

LUISANDER C. LUY
BAC Chairperson/OIC-ASDS

DEPARTMENT OF EDUCATION
EDUCATION FACILITIES DIVISION
DepEd Complex, Meralco Avenue, Pasig City

BILL OF QUANTITIES

School	**: Labo Central School**	**Date:**	
School I.D	**: 128172**	**Bid Amount:**	
Region	**: X - Northern Mindanao**	**Engineering and Administrative Overhead:**	**-**
Division	**: OZAMIZ City**	**Approved Budget for the Contract:**	**6,181,684.19**
Project Title	**:**	**Completion Period:**	120 Caledar Days
CONSERVATION AND RESTORATION OF GABALDON SCHOOL BUILDING		**Minimum Required Manpower:**	
		General Foreman	
		Skilled Laborer	
		Unskilled Laborer	
Location	: Brgy. Labo, Ozamiz City	**Minimum Required Equipment:**	
		Hand Tools / Welding Machine / Plate Compactor (5hp)	
		One-Bagger Mixer / Bar Cutter	

Item No.	Description	% of Total	Unit	Quantity	Direct Cost		Adjusted Unit Cost	Adjusted Total Cost
					Total Cost	Unit Cost		
(1)	(2)	(3)	(4)	(5)	(6)	(7) (6) / (5)	(8) (9) / (5)	(9)
A.	**Facilities for the Engineer**							
A.1	Temporary Facilities		Month	4.00				
B.	**Other General Requirements**							
B.1	Fire Safety Inspection Certificate (FSIC)		lot	1.00				
SPL 1	Project Billboard		Each	1.00				
SPL 2	Construction Safety and Health		Month	4.00				
C.	**Mobilization and Demobilization**							
C.1	Mobilization and Demobilization		Ls	1.00				
1.0000	**Earthworks**							
1 (a)	Clearing and Grubbing		sq.m	216.00				
1 (b)	Structural Excavation		cu.m	4.50				
1 (c)	Backfilling of Excavated Materials		cu.m	16.11				
1 (d)	Gravel Bedding G-1		cu m	1.04				
	Termite Control Works							
1 (f)	Soil Poisoning		L	88.00				
2.0000	**Concreting Works (3000 psi)**							
	(new concrete works / jacketting works)							
2 (i)	Retrofitting/Jacketting of Concrete Pedestal		cu m	30.78				
2 (h)	Ramp on Fill		cu m	1.74				
3.0000	**Rebar Works**							
3 (a)	Reinforcing Steel Bar, Grade 40		kg	603.06				
5.0000	**Masonry Works**							
5 (f)	Concrete Pavers		sq.m	132.00				
	Finishing Works							
5 (d)	Plain Cement Plaster Finish		sq.m	33.00				
5 (e)	Plain Cement Floor/Topping Finish		sq.m	216.00				
6.0000	**Fabricated Materials and Hardware**							
6 (b)	Removal of Window with Jamb		sq m	180.73				
6 (e)	Capiz window		set	16.00				
6 (g)	Ramp Rail		Ls	1.00				
6 (i)	Refurbishment of Wooden Door		set	4.00				
8.0000	**Roofing Works**							
8 (a)	Removal of Metal Roofing		sq m	338.00				
8 (b)	Pre - painted Metal Sheets (Corrugated, Short Span/ Long Span, below 0.427 BMT/ above 0.427 BMT		sq.m	338.00				
8 (e)	Fabricated Metal Roofing Accessory (Ridge/ Hip Rolls/ Flashing/ Counter Flashing/ Valley Roll)		m	25.00				
9.0000	**Ceiling and Carpentry Works**							
9 (a)	Removal of Wooden Truss/ Beams		bd.ft	4,794.67				
9 (b)	Removal of Wooden Purlins		bd.ft	840.00				
9 (c)	Removal of Partition		sq m	290.50				
9 (d)	Removal of Ceiling		sq m	290.50				
9 (m)	Wooden Ceiling (Interior & exterior)		sq.m	290.00				
9 (o)	Wooden Partition (Interior & Hallway)		sq.m	290.50				
9 (q)	Structural Wooden Roof Truss		ls	1.00				
9 (i)	Blackboard		sq.m	27.46				
9 (j)	Structural Wooden Roofing Frame		Ls	1.00				
10.0000	**Electrical Works**							
10 (a)	Conduit, Boxes and Fitting		Ls	1.00				
10 (b)	Wires and Wiring Devices		Ls	1.00				

Item No.	Description	% of Total	Unit	Quantity	Direct Cost		Adjusted Unit Cost	Adjusted Total Cost
					Total Cost	Unit Cost		
10 (c)	Lighting Fixture/ Fixture		Ls	1.00				
10 (d)	Panel Board and Cabinets		Ls	1.00				
13.0000	**Painting Works**							
13 (a)	Masonry Painting		sq.m	216.00				
13 (b)	Wooden Painting		sq.m	870.00				
16.0000	**Historical Marker and Road Signage**							
16 (a)	Historical Marker with Pedestal		Ls	1.00				
16 (b)	Reflectorized Road Signage		Ls	1.00				

Prepared by:

Contractor